

PAUL STRESING ASSOCIATES, INC.

ARCHITECTURE • SPACE PLANNING • INTERIOR DESIGN

E-mail: PSA@PaulStresingAssociates.com

14617 Main Street, Alachua, Florida 32615

Telephone (386) 462-6407

Paul R. Stresing, President
Certificate of Authorization No. AA-0003377
Florida Architectural License No. AR0013985

American Institute of Architects
National Council of Architectural
Registration Boards

ADDENDUM NO. 1 THE DRAWINGS & PROJECT MANUAL FOR HIGH SPRINGS PROTOTYPE STORAGE/RESTROOM BUILDING DATED DECEMBER 20, 2018 PSA 18-738

The above-referenced Drawings and Project Manual are hereby modified, corrected, and/or supplemented as follows:

1) Project Manual Section 01010 Summary of Work

- A. At Subsection 1.02 (1) Site Work, add the following:
Contractor to include in their bid a \$15,000.00 allowance to install a small grinder pump/lift station to accommodate the sanitary sewer generated by the new facility. The exact location will be determined during the projects preconstruction meeting and allowance will include installation and service connections.
- B. At Subsection 1.02 (3) Building, make the following changes:
Delete reference to split face block and add the following:
Base Bid - Exterior reinforced CMU wall system to be regular weight block with a three coat stucco veneer with control joints provided during shop drawing submission. Finish coat to be a through-the-product color characteristic. Entry screen wall is to have precast concrete caps.
Deductive Alternate - Exterior reinforced CMU wall system to be regular weight CMU with intermediate vertical score and exterior to be painted two different colors (dark wainscot and lighter upper portion of the wall). Top of screen walls are to have a grout radiused wash at its top surface.

2) Project Manual Section 01100 Alternates/Substitutions

- A. At Subsection 2.0 add the following:
2.03 Deductive Alternate No. 3 - Provide a credit representing the cost difference from the back bid stucco finish to the following: Exterior wall assembly to be regular weight CMU with intermediate vertical score and top of screen wall to have a grout buildup wash at top surface and all surfaces sealed and painted with two tone color scheme determined during shop drawing submission.

END OF ADDENDUM NO. 1

TOTAL NO. OF PAGES WITH ATTACHMENTS = (1) (If any pages of this Addendum are missing or illegible, it is the Contractor's responsibility to contact Paul Stresing Associates, Inc. (386) 462-6407 to request missing or illegible pages.)